

City of Holy Cross
City Hall
938 Church Street
Holy Cross, IA 52053

To: Bidding Document Holders of Record

The information contained in this Addendum modifies, supplements or replaces information contained in the Project Manual and on the Drawings and is hereby made a part of the Contract Documents.

This addendum contains 3 pages, including four clarifications and a header change. No quantity items were added or modified.

Enclosed with this Addendum is a revised section 00300 and clarifications.

PROJECT MANUAL ITEM

Clarifications:

- 1. Plastic Storm Sewer Pipe:** Where storm sewer pipe material is specified as plastic, pipe material can be PVC, HDPE, or equivalent.
- 2. Storm Sewer Pipe Envelop:** For all storm sewer pipes, backfill shall be drainable backfill 1' above the Pipe
- 3. Storm Sewer Apron:** This item is incidental to the 15" plastic storm sewer pipe.
- 4. Water Main Tees:** Incidental to 6" Water Main

Section 00300:

Sheet 300-A, the columns for Quantity and Units were switched to be shown correctly. Corrected Sheet 300-A is attached following this document.

End of Addendum No. 1

UNIT PRICE BID
Holy Cross Subdivision No. 2
Holy Cross, Iowa

The following prices per item shall be for furnishing and installing the various items of material and Work as specified and shown on the Drawings. Bidder agrees to perform all Work as shown on the Drawings and described in the Specifications for the following listed prices. Bidder acknowledges that unit prices have been computed in accordance with paragraph 11.01 of the General Conditions. Bidder acknowledges that quantities are not guaranteed and final payment will be based on actual quantities, and classifications are to be made by ENGINEER as provided in paragraph 11.01 of the General Conditions.

NOTE: A price must be bid for each item in the Bid, even though the estimated quantity is zero. Unbalanced or unreasonable unit prices may cause rejection of the Bid. All numbers shall be in ink.

Legal Name of Bidder: _____

Address of Bidder: _____

NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE BID	
				(Numbers)	EXTENSION
1	Mobilization	1	LS		\$
2	Trench Compaction Testing	1	LS		\$
3	Subgrade and Subbase Compaction Testing	1	LS		\$
4	Traffic Control	1	LS		\$
5	Permanent Signs	8	EA		\$
6	Sign Posts	8	EA		\$
7	Temporary Erosion and Sediment Controls (Including Silt Fence)	1	LS		\$
8	Remove Fence (950 lf)	1	LS		\$
9	Rock Excavation	200	CY		\$
10	Unclassified Excavation and Embankment	5,000	CY		\$
11	Strip and Respread Topsoil	2,000	CY		\$
12	Subgrade Preparation	5,272	SY		\$
13	Subbase	5,077	SY		\$
14	Storm Sewer Main, 15-Inch Dia. RCP	269	LF		\$
15	Storm Sewer Main, 15-Inch Dia. Plastic	881	LF		\$
16	Storm Sewer Main, 18-Inch Dia. RCP	25	LF		\$
17	Storm Sewer Main, 18-Inch Dia. Plastic	184	LF		\$
18	Bee-Hive Intake	1	EA		\$
19	Subdrain, 6" (wrapped with fabric), and 17 Service T's	2,650	LF		\$
20	Subdrain Cleanouts	8	EA		\$
21	Storm Sewer Manholes	2	EA		\$
22	Storm Sewer Intakes (101-B)	7	EA		\$
23	Storm Sewer Intakes (104-B)	4	EA		\$
24	Water Main, C900 6"	1,359	LF		\$
25	Valve and Box (6" Gate)	5	EA		\$
26	45 Deg Bend	4	EA		\$
27	Water Services (1" Trenched) (Total 17 Services, 660 lf)	17	Ea		\$

NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE BID	
				(Numbers)	EXTENSION
28	Fire Hydrant Assembly	3	EA		\$
29	Fire Hydrant to be Relocated	2	EA		\$
30	Disinfection and Hydrostatic Testing	1	LS		\$
31	Sanitary Sewer Manholes	3	EA		\$
32	Sanitary Sewer Manholes to be Relocated	1	EA		\$
33	Sanitary Sewer Main 8" Truss	1,047	LF		\$
34	Sanitary Sewer Services (4" Trenched) (Total 17 Services, 580 LF)	17	EA		\$
35	Portland Cement Concrete Pavement, Non-Reinforced (7")	4,615	SY		\$
36	Seeding	1	LS		\$

TOTAL BID

COMPUTED TOTAL BID CONTRACT (Items __ THROUGH __)

(Words) \$ (Numbers)